

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- 01 Underground Feeder Conduit ---								
--- Primary Conduit ---								
1220	4" PVC (2-Parallel)	60	138.00	C	82.80	3.20	C	1.92
2091	4" PVC Bell End	2	280.75	C	5.62	0.22	E	0.44
2123	4" PVC Coupling	2	116.30	C	2.33	0.11	E	0.22
2135	4" PVC Elbow	2	656.52	C	13.13	0.75	E	1.50
7089	36"Wx48"D Trench-Back Hoe	60	OPEN		0.00	24.00	C	14.40
7104	6'x6'x6' Manhole Excavate/Backfill/Comp.	1	45.00	E	45.00	24.00	E	24.00
7126	36"Wx48"D Backfill & Compaction	60	0.00	E	0.00	40.00	C	24.00
7140	6'x8' Concrete Trans Pad w/Handhole	1	OPEN		0.00	10.00	E	10.00
--- Primary Conduit Total ---					148.88			76.48
--- Secondary Conduit ---								
1221	5" PVC (2-Parallel)	120	189.00	C	226.80	3.60	C	4.32
2092	5" PVC Bell End	2	449.98	C	9.00	0.24	E	0.48
2124	5" PVC Coupling	2	386.32	C	7.73	0.12	E	0.24
2136	5" PVC Elbow	2	1,440.76	C	28.82	1.00	E	2.00
7089	36"Wx48"D Trench-Back Hoe	120	OPEN		0.00	24.00	C	28.80
7126	36"Wx48"D Backfill & Compaction	120	0.00	E	0.00	40.00	C	48.00
--- Secondary Conduit Total ---					272.35			83.84
--- CATV Conduit ---								
1194	3" PVC Conduit	190	97.80	C	185.82	3.25	C	6.18
2089	3" PVC Bell End	2	221.16	C	4.42	0.18	E	0.36
2121	3" PVC Coupling	2	105.05	C	2.10	0.09	E	0.18
2133	3" PVC Elbow	2	398.08	C	7.96	0.50	E	1.00
--- CATV Conduit Total ---					200.30			7.72
--- Telephone Conduit ---								
1196	4" PVC Conduit	190	138.00	C	262.20	4.00	C	7.60
2091	4" PVC Bell End	2	280.75	C	5.62	0.22	E	0.44
--- Telephone Conduit Total ---					267.82			8.04
--- 01 Underground Feeder Conduit Total ---					889.35			176.08
--- 02 Underground Branch Conduit ---								
--- A-33,39 Parking Lot Lighting ---								
1182	3/4" PVC Conduit	80	24.65	C	19.72	1.50	C	1.20
1188	3/4" PVC Conduit	640	16.20	C	103.68	1.50	C	9.60
1831	3/4" GRC Coupling	1	102.42	C	1.02	0.06	E	0.06
2075	3/4" PVC Male Adaptor	17	22.07	C	3.75	0.05	E	0.85
2115	3/4" PVC Coupling	16	9.78	C	1.56	0.03	E	0.48
2127	3/4" PVC Elbow	16	34.90	C	5.58	0.09	E	1.44
2129	3/4" PVC Coupling	48	13.06	C	6.27	0.03	E	1.44
2141	3/4" PVC Elbow	16	45.32	C	7.25	0.09	E	1.44
5049	Pole Base Anchor Bolt & Nuts	32	OPEN		0.00	0.15	E	4.80
5061	30"x4' Sono-Tube (96" Hole)	8	OPEN		0.00	6.75	E	54.00
5067	Dig Pole Base Hole-30"x96" Deep	8	280.00	E	2,240.00	2.00	E	16.00
5296	Pole Base Anchor Bolt & Nuts	32	OPEN		0.00	OPEN		0.00
5304	24"x4' Sono-Tube (60" hole)	8	OPEN		0.00	5.15	E	41.20
5310	Dig Pole Base Hole-24"x60" Deep	8	0.00	E	0.00	OPEN		0.00
5604	5 Sack Concrete (Cu. Yards)	8	OPEN		0.00	0.50	E	3.76
6164	#4 Re-Bar	416	OPEN		0.00	5.00	C	20.80

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
6870	#4 Re-Bar	928	OPEN		0.00	5.00	C	46.40
7067	6"Wx24"D Trench-Ditch Witch	620	0.00	E	0.00	3.00	C	18.60
7110	6"Wx24"D Backfill & Compaction	620	0.00	E	0.00	5.00	C	31.00
7133	5 Sack Concrete (Cu. Yards)	16	90.00	E	1,440.00	0.50	E	8.00
--- A-33,39 Parking Lot Lighting Total ---					3,828.83			261.07
--- FA ZN-1,2 Water Flow/Tamper SW ---								
1188	3/4" PVC Conduit	125	16.20	C	20.25	1.50	C	1.88
2073	3/4" PVC Female Adaptor	2	18.23	C	0.36	0.05	E	0.10
2115	3/4" PVC Coupling	2	9.78	C	0.20	0.03	E	0.06
2127	3/4" PVC Elbow	2	34.90	C	0.70	0.09	E	0.18
7067	6"Wx24"D Trench-Ditch Witch	30	0.00	E	0.00	3.00	C	0.90
7110	6"Wx24"D Backfill & Compaction	30	0.00	E	0.00	5.00	C	1.50
8171	3/4" PVC (Schedule-80)	10	27.32	C	2.73	1.75	C	0.18
--- FA ZN-1,2 Water Flow/Tamper SW Total --					24.24			4.80
--- 02 Underground Branch Conduit Total ---					3,853.07			265.87
--- 03 Aboveground Feeder Conduit ---								
--- Panel A ---								
1006	2-1/2" EMT	16	262.20	C	41.95	5.00	C	0.80
1343	2-1/2" EMT Elbow	2	1,502.94	C	30.06	0.50	E	1.00
1442	2-1/2" Set Screw Steel Conn	2	385.84	C	7.72	0.17	E	0.34
1562	2-1/2" Set Screw Steel Cplg	4	309.01	C	12.36	0.14	E	0.56
1604	2-1/2" Plastic Bushing	2	70.09	C	1.40	0.04	E	0.08
2341	2-1/2" Unistrut Strap	4	933.45	C	37.34	10.00	C	0.40
6643	Unistrut (Shallow)	10	146.77	C	14.68	9.71	C	0.97
--- Panel A Total ---					145.51			4.15
--- Panel M ---								
1006	2-1/2" EMT	12	262.20	C	31.46	5.00	C	0.60
1343	2-1/2" EMT Elbow	2	1,502.94	C	30.06	0.50	E	1.00
1442	2-1/2" Set Screw Steel Conn	2	385.84	C	7.72	0.17	E	0.34
1562	2-1/2" Set Screw Steel Cplg	4	309.01	C	12.36	0.14	E	0.56
1604	2-1/2" Plastic Bushing	2	70.09	C	1.40	0.04	E	0.08
2341	2-1/2" Unistrut Strap	4	933.45	C	37.34	10.00	C	0.40
--- Panel M Total ---					120.34			2.98
--- Panel B ---								
1004	1-1/2" EMT	20	125.69	C	25.14	3.25	C	0.65
1341	1-1/2" EMT Elbow	2	378.22	C	7.56	0.30	E	0.60
1440	1-1/2" Set Screw Steel Conn	2	99.63	C	1.99	0.12	E	0.24
1560	1-1/2" Set Screw Steel Cplg	4	111.99	C	4.48	0.11	E	0.44
1602	1-1/2" Plastic Bushing	2	17.38	C	0.35	0.02	E	0.04
--- Panel B Total ---					39.52			1.97
--- 03 Aboveground Feeder Conduit Total ---					305.37			9.10
--- 04 Aboveground Branch Conduit ---								
--- A-10,12 Future Oven ---								
1001	3/4" EMT	42	39.93	C	16.77	2.60	C	1.09
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	4	19.21	C	0.81	0.06	E	0.25

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2279	3/4" 1-Hole Strap	5	8.42	C	0.44	2.29	C	0.12
2577	4-11/16" Square Box w/brkt Comb KO's	1	377.06	C	3.77	0.25	E	0.25
2759	4-11/16"-1G Plaster Ring-5/8"D	1	121.90	C	1.22	0.08	E	0.08
8068	10x1" TEK Screw	8	6.94	C	0.56	0.01	E	0.08
8261	Grndscr&Bare Pigtail	1	67.78	C	0.68	1.20	C	0.01
--- A-10,12 Future Oven Total ---					24.62			2.00
--- A-13,15 Dryer ---								
1001	3/4" EMT	33	39.93	C	13.18	2.60	C	0.86
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	4	19.21	C	0.81	0.06	E	0.25
2279	3/4" 1-Hole Strap	4	8.42	C	0.36	2.29	C	0.10
2577	4-11/16" Square Box w/brkt Comb KO's	1	377.06	C	3.77	0.25	E	0.25
2759	4-11/16"-1G Plaster Ring-5/8"D	1	121.90	C	1.22	0.08	E	0.08
8068	10x1" TEK Screw	7	6.94	C	0.49	0.01	E	0.07
8261	Grndscr&Bare Pigtail	1	67.78	C	0.68	1.20	C	0.01
--- A-13,15 Dryer Total ---					20.88			1.74
--- A-17,19 Receptacle ---								
1000	1/2" EMT	112	21.66	C	24.26	2.50	C	2.80
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	11	12.09	C	1.35	0.05	E	0.56
2278	1/2" 1-Hole Strap	14	5.55	C	0.78	2.29	C	0.32
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	1	82.66	C	0.83	0.18	E	0.18
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
4790	4" Square Flat Blank Cover	1	25.73	C	0.26	0.07	E	0.07
8068	10x1" TEK Screw	19	6.94	C	1.32	0.01	E	0.19
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
--- A-17,19 Receptacle Total ---					33.81			4.88
--- A-35,37 Fire Alarm, GWH-1 ---								
1000	1/2" EMT	131	21.66	C	28.37	2.50	C	3.28
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	11	12.09	C	1.35	0.05	E	0.56
2278	1/2" 1-Hole Strap	16	5.55	C	0.89	2.29	C	0.37
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
8068	10x1" TEK Screw	21	6.94	C	1.46	0.01	E	0.21
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
--- A-35,37 Fire Alarm, GWH-1 Total ---					37.08			5.18
--- A-36,38 Dishwasher, Microwave ---								
1000	1/2" EMT	78	21.66	C	16.89	2.50	C	1.95
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	8	12.09	C	0.97	0.05	E	0.40
2278	1/2" 1-Hole Strap	14	5.55	C	0.78	2.29	C	0.32
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
8068	10x1" TEK Screw	19	6.94	C	1.32	0.01	E	0.19
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
--- A-36,38 Dishwasher, Microwave Total ---					24.97			3.62

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- B-1,14,16 Bbd Heat, Receptacle ---								
1000	1/2" EMT	170	21.66	C	36.82	2.50	C	4.25
1001	3/4" EMT	126	39.93	C	50.31	2.60	C	3.28
1436	1/2" Set Screw Steel Conn	24	11.49	C	2.76	0.05	E	1.20
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1556	1/2" Set Screw Steel Cplg	19	12.09	C	2.30	0.05	E	0.95
1557	3/4" Set Screw Steel Cplg	13	19.21	C	2.42	0.06	E	0.76
2278	1/2" 1-Hole Strap	20	5.55	C	1.11	2.29	C	0.46
2279	3/4" 1-Hole Strap	16	8.42	C	1.33	2.29	C	0.36
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	12	126.49	C	15.18	0.20	E	2.40
2577	4-11/16" Square Box w/brkt Comb KO's	1	377.06	C	3.77	0.25	E	0.25
2731	4" Square-1G Plaster Ring-5/8"D	12	33.13	C	3.98	0.07	E	0.84
2759	4-11/16"-1G Plaster Ring-5/8"D	1	121.90	C	1.22	0.08	E	0.08
6839	Red Wirenuts	39	109.34	M	4.26	1.75	C	0.68
8068	10x1" TEK Screw	73	6.94	C	5.07	0.01	E	0.73
8261	Grndscr&Bare Pigtail	13	67.78	C	8.81	1.20	C	0.16
--- B-1,14,16 Bbd Heat, Receptacle Total ---					139.71			16.52
--- B-7,9,11 Receptacle ---								
1000	1/2" EMT	490	21.66	C	106.13	2.50	C	12.25
1436	1/2" Set Screw Steel Conn	24	11.49	C	2.76	0.05	E	1.20
1556	1/2" Set Screw Steel Cplg	52	12.09	C	6.29	0.05	E	2.60
2278	1/2" 1-Hole Strap	14	5.55	C	0.78	2.29	C	0.32
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	12	126.49	C	15.18	0.20	E	2.40
2731	4" Square-1G Plaster Ring-5/8"D	12	33.13	C	3.98	0.07	E	0.84
6839	Red Wirenuts	36	109.34	M	3.94	1.75	C	0.63
8068	10x1" TEK Screw	91	6.94	C	6.32	0.01	E	0.91
8261	Grndscr&Bare Pigtail	12	67.78	C	8.13	1.20	C	0.14
--- B-7,9,11 Receptacle Total ---					153.51			21.29
--- B-10,12,13 Receptacle ---								
1000	1/2" EMT	436	21.66	C	94.44	2.50	C	10.90
1436	1/2" Set Screw Steel Conn	30	11.49	C	3.45	0.05	E	1.50
1556	1/2" Set Screw Steel Cplg	48	12.09	C	5.80	0.05	E	2.40
2278	1/2" 1-Hole Strap	47	5.55	C	2.61	2.29	C	1.08
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	15	126.49	C	18.97	0.20	E	3.00
2731	4" Square-1G Plaster Ring-5/8"D	15	33.13	C	4.97	0.07	E	1.05
6839	Red Wirenuts	45	109.34	M	4.92	1.75	C	0.79
8068	10x1" TEK Screw	93	6.94	C	6.45	0.01	E	0.93
8261	Grndscr&Bare Pigtail	15	67.78	C	10.17	1.20	C	0.18
--- B-10,12,13 Receptacle Total ---					151.78			21.83
--- B-15,17 Receptacle ---								
1000	1/2" EMT	242	21.66	C	52.42	2.50	C	6.05
1436	1/2" Set Screw Steel Conn	16	11.49	C	1.84	0.05	E	0.80
1556	1/2" Set Screw Steel Cplg	26	12.09	C	3.14	0.05	E	1.30
2278	1/2" 1-Hole Strap	28	5.55	C	1.55	2.29	C	0.64
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	8	126.49	C	10.12	0.20	E	1.60
2731	4" Square-1G Plaster Ring-5/8"D	8	33.13	C	2.65	0.07	E	0.56
6839	Red Wirenuts	32	109.34	M	3.50	1.75	C	0.56
8068	10x1" TEK Screw	52	6.94	C	3.61	0.01	E	0.52
8261	Grndscr&Bare Pigtail	8	67.78	C	5.42	1.20	C	0.10
--- B-15,17 Receptacle Total ---					84.25			12.13

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- B-24,25,27 Microwave, Receptac ---								
1000	1/2" EMT	143	21.66	C	30.97	2.50	C	3.58
1436	1/2" Set Screw Steel Conn	16	11.49	C	1.84	0.05	E	0.80
1556	1/2" Set Screw Steel Cplg	17	12.09	C	2.06	0.05	E	0.85
2278	1/2" 1-Hole Strap	17	5.55	C	0.94	2.29	C	0.39
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	8	126.49	C	10.12	0.20	E	1.60
2731	4" Square-1G Plaster Ring-5/8"D	8	33.13	C	2.65	0.07	E	0.56
6839	Red Wirenuts	28	109.34	M	3.06	1.75	C	0.49
8068	10x1" TEK Screw	41	6.94	C	2.85	0.01	E	0.41
8261	Grndscr&Bare Pigtail	8	67.78	C	5.42	1.20	C	0.10
--- B-24,25,27 Microwave, Receptac Total ---					59.91			8.78
--- B-3,4 Freezer, Refrigerator ---								
1000	1/2" EMT	47	21.66	C	10.18	2.50	C	1.18
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	5	12.09	C	0.60	0.05	E	0.25
2278	1/2" 1-Hole Strap	5	5.55	C	0.28	2.29	C	0.11
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
6839	Red Wirenuts	8	109.34	M	0.87	1.75	C	0.14
8068	10x1" TEK Screw	11	6.94	C	0.76	0.01	E	0.11
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
--- B-3,4 Freezer, Refrigerator Total ---					17.70			2.55
--- B-19,21,6 Receptacle, Refer ---								
1000	1/2" EMT	300	21.66	C	64.98	2.50	C	7.50
1436	1/2" Set Screw Steel Conn	20	11.49	C	2.30	0.05	E	1.00
1556	1/2" Set Screw Steel Cplg	36	12.09	C	4.35	0.05	E	1.80
2278	1/2" 1-Hole Strap	36	5.55	C	2.00	2.29	C	0.82
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	10	126.49	C	12.65	0.20	E	2.00
2731	4" Square-1G Plaster Ring-5/8"D	10	33.13	C	3.31	0.07	E	0.70
6839	Red Wirenuts	30	109.34	M	3.28	1.75	C	0.53
8068	10x1" TEK Screw	66	6.94	C	4.58	0.01	E	0.66
8261	Grndscr&Bare Pigtail	10	67.78	C	6.78	1.20	C	0.12
--- B-19,21,6 Receptacle, Refer Total ---					104.23			15.13
--- B-8,28,30 Refrigerator, Recept ---								
1000	1/2" EMT	65	21.66	C	14.08	2.50	C	1.63
1436	1/2" Set Screw Steel Conn	6	11.49	C	0.69	0.05	E	0.30
1556	1/2" Set Screw Steel Cplg	7	12.09	C	0.85	0.05	E	0.35
2278	1/2" 1-Hole Strap	7	5.55	C	0.39	2.29	C	0.16
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	3	126.49	C	3.79	0.20	E	0.60
2731	4" Square-1G Plaster Ring-5/8"D	3	33.13	C	0.99	0.07	E	0.21
6839	Red Wirenuts	12	109.34	M	1.31	1.75	C	0.21
8068	10x1" TEK Screw	16	6.94	C	1.11	0.01	E	0.16
8261	Grndscr&Bare Pigtail	3	67.78	C	2.03	1.20	C	0.04
--- B-8,28,30 Refrigerator, Recept Total ---					25.24			3.66
--- B-29 Exterior Receptacles ---								
1000	1/2" EMT	360	21.66	C	77.98	2.50	C	9.00
1436	1/2" Set Screw Steel Conn	12	11.49	C	1.38	0.05	E	0.60
1556	1/2" Set Screw Steel Cplg	42	12.09	C	5.08	0.05	E	2.10
2278	1/2" 1-Hole Strap	42	5.55	C	2.33	2.29	C	0.96

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	6	126.49	C	7.59	0.20	E	1.20
2731	4" Square-1G Plaster Ring-5/8"D	6	33.13	C	1.99	0.07	E	0.42
6839	Red Wirenuts	18	109.34	M	1.97	1.75	C	0.32
8068	10x1" TEK Screw	60	6.94	C	4.16	0.01	E	0.60
8261	Grndscr&Bare Pigtail	6	67.78	C	4.07	1.20	C	0.07
--- B-29 Exterior Receptacles Total ---					106.55			15.27

--- B-22 EDF-1 ---								
1000	1/2" EMT	59	21.66	C	12.78	2.50	C	1.48
1436	1/2" Set Screw Steel Conn	2	11.49	C	0.23	0.05	E	0.10
1556	1/2" Set Screw Steel Cplg	6	12.09	C	0.73	0.05	E	0.30
2278	1/2" 1-Hole Strap	7	5.55	C	0.39	2.29	C	0.16
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	1	126.49	C	1.26	0.20	E	0.20
2731	4" Square-1G Plaster Ring-5/8"D	1	33.13	C	0.33	0.07	E	0.07
8068	10x1" TEK Screw	10	6.94	C	0.69	0.01	E	0.10
8261	Grndscr&Bare Pigtail	1	67.78	C	0.68	1.20	C	0.01
--- B-22 EDF-1 Total ---					17.09			2.42

--- B-18,26 Receptacle, Time Clock ---								
1000	1/2" EMT	48	21.66	C	10.40	2.50	C	1.20
1436	1/2" Set Screw Steel Conn	8	11.49	C	0.92	0.05	E	0.40
1556	1/2" Set Screw Steel Cplg	5	12.09	C	0.60	0.05	E	0.25
1586	1/2" Locknut	4	10.37	C	0.41	0.01	E	0.04
1672	1/2" Offset Nipple	2	357.61	C	7.15	0.08	E	0.16
2278	1/2" 1-Hole Strap	6	5.55	C	0.33	2.29	C	0.14
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	4	82.66	C	3.31	0.18	E	0.72
6381	SPST 40A/120V 7-Day Time Switch	2	87.42	E	174.84	1.40	E	2.80
6398	4"x4"x2' Wireway-Nema 1	1	13.74	E	13.74	0.14	E	0.14
6839	Red Wirenuts	12	109.34	M	1.31	1.75	C	0.21
8063	10x1" HEX HD Sheetmetal Screw	16	3.41	C	0.55	0.01	E	0.16
8261	Grndscr&Bare Pigtail	4	67.78	C	2.71	1.20	C	0.05
--- B-18,26 Receptacle, Time Clock Total ---					216.27			6.27

--- B-2,20 Receptacles ---								
1000	1/2" EMT	104	21.66	C	22.53	2.50	C	2.60
1436	1/2" Set Screw Steel Conn	8	11.49	C	0.92	0.05	E	0.40
1556	1/2" Set Screw Steel Cplg	11	12.09	C	1.33	0.05	E	0.55
2278	1/2" 1-Hole Strap	12	5.55	C	0.67	2.29	C	0.27
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	4	126.49	C	5.06	0.20	E	0.80
2731	4" Square-1G Plaster Ring-5/8"D	4	33.13	C	1.33	0.07	E	0.28
6839	Red Wirenuts	8	109.34	M	0.87	1.75	C	0.14
8068	10x1" TEK Screw	24	6.94	C	1.67	0.01	E	0.24
8261	Grndscr&Bare Pigtail	4	67.78	C	2.71	1.20	C	0.05
--- B-2,20 Receptacles Total ---					37.09			5.33

--- M-1,3,5 AC-1 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-1,3,5 AC-1 Total ---					54.17			3.79
--- M-7,9,11 AC-2 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-7,9,11 AC-2 Total ---					54.17			3.79
--- M-13,15,17 AC-3 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1586	1/2" Locknut	2	10.37	C	0.21	0.01	E	0.02
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1672	1/2" Offset Nipple	1	357.61	C	3.58	0.08	E	0.08
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
2579	1G WP Bell Box-(3)1/2" Hubs	1	210.98	C	2.11	0.30	E	0.30
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-13,15,17 AC-3 Total ---					60.07			4.19
--- M-19,21,23 AC-4 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-19,21,23 AC-4 Total ---					54.17			3.79
--- M-2,4,6 AC-5 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-2,4,6 AC-5 Total ---					54.17			3.79
--- M-8,10,12 AC-6 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1586	1/2" Locknut	2	10.37	C	0.21	0.01	E	0.02
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1672	1/2" Offset Nipple	1	357.61	C	3.58	0.08	E	0.08
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
2579	1G WP Bell Box-(3)1/2" Hubs	1	210.98	C	2.11	0.30	E	0.30
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-8,10,12 AC-6 Total ---					60.07			4.19
--- M-14,16,18 AC-7 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-14,16,18 AC-7 Total ---					54.17			3.79
--- M-20,22,24 AC-8 ---								
1001	3/4" EMT	85	39.93	C	33.94	2.60	C	2.21
1144	3/4" Liquidtight (metallic)	5	131.08	C	6.55	2.00	C	0.10
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1557	3/4" Set Screw Steel Cplg	9	19.21	C	1.63	0.06	E	0.51
1587	3/4" Locknut	1	13.97	C	0.14	0.01	E	0.01
1599	3/4" Plastic Bushing	1	6.69	C	0.07	0.01	E	0.01
1754	3/4" Chase Nipple	1	44.34	C	0.44	0.06	E	0.06
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
2336	3/4" Unistrut Strap	11	41.11	C	4.37	5.00	C	0.53
8068	10x1" TEK Screw	6	6.94	C	0.42	0.01	E	0.06
--- M-20,22,24 AC-8 Total ---					54.17			3.79
--- A-31 Duct Smoke Detectors ---								
1000	1/2" EMT	177	21.66	C	38.34	2.50	C	4.43
1121	1/2" Steel Flex	5	42.25	C	2.11	1.75	C	0.09
1436	1/2" Set Screw Steel Conn	16	11.49	C	1.84	0.05	E	0.80

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
1556	1/2" Set Screw Steel Cplg	18	12.09	C	2.14	0.05	E	0.89
1878	1/2" Die Cast Screw-In Flex Conn	16	26.32	C	4.21	0.07	E	1.12
2278	1/2" 1-Hole Strap	22	5.55	C	1.23	2.29	C	0.51
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	8	82.66	C	6.61	0.18	E	1.44
4790	4" Square Flat Blank Cover	8	25.73	C	2.06	0.07	E	0.56
--- A-31 Duct Smoke Detectors Total ---					58.54			9.84
--- Door Bell ---								
1000	1/2" EMT	36	21.66	C	7.80	2.50	C	0.90
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	4	12.09	C	0.48	0.05	E	0.20
1586	1/2" Locknut	2	10.37	C	0.21	0.01	E	0.02
1598	1/2" Plastic Bushing	1	5.57	C	0.06	0.01	E	0.01
1753	1/2" Chase Nipple	1	50.36	C	0.50	0.05	E	0.05
2278	1/2" 1-Hole Strap	4	5.55	C	0.22	2.29	C	0.09
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	1	82.66	C	0.83	0.18	E	0.18
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
4790	4" Square Flat Blank Cover	1	25.73	C	0.26	0.07	E	0.07
8068	10x1" TEK Screw	10	6.94	C	0.69	0.01	E	0.10
--- Door Bell Total ---					14.70			2.36
--- DVR System ---								
1000	1/2" EMT	110	21.66	C	23.83	2.50	C	2.75
1436	1/2" Set Screw Steel Conn	6	11.49	C	0.69	0.05	E	0.30
1556	1/2" Set Screw Steel Cplg	12	12.09	C	1.45	0.05	E	0.60
2278	1/2" 1-Hole Strap	12	5.55	C	0.67	2.29	C	0.27
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	1	82.66	C	0.83	0.18	E	0.18
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	3	126.49	C	3.79	0.20	E	0.60
2702	11-1/2"-18-1/2" Bar Hanger w/clip	1	268.87	C	2.69	0.11	E	0.11
2731	4" Square-1G Plaster Ring-5/8"D	4	33.13	C	1.33	0.07	E	0.28
8068	10x1" TEK Screw	21	6.94	C	1.46	0.01	E	0.21
--- DVR System Total ---					36.74			5.30
--- B-23 Wireless Transmitter ---								
1000	1/2" EMT	100	21.66	C	21.66	2.50	C	2.50
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	11	12.09	C	1.33	0.05	E	0.55
2278	1/2" 1-Hole Strap	12	5.55	C	0.67	2.29	C	0.27
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
6839	Red Wirenuts	4	109.34	M	0.44	1.75	C	0.07
8068	10x1" TEK Screw	18	6.94	C	1.25	0.01	E	0.18
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
--- B-23 Wireless Transmitter Total ---					30.36			4.33
--- Handkey Unit ---								
1000	1/2" EMT	190	21.66	C	41.15	2.50	C	4.75
1436	1/2" Set Screw Steel Conn	6	11.49	C	0.69	0.05	E	0.30
1556	1/2" Set Screw Steel Cplg	20	12.09	C	2.42	0.05	E	1.00
2278	1/2" 1-Hole Strap	22	5.55	C	1.22	2.29	C	0.50
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
8068	10x1" TEK Screw	28	6.94	C	1.94	0.01	E	0.28
	--- Handkey Unit Total ---				50.61			7.37
--- Entrance Release ---								
1000	1/2" EMT	85	21.66	C	18.41	2.50	C	2.13
1436	1/2" Set Screw Steel Conn	10	11.49	C	1.15	0.05	E	0.50
1556	1/2" Set Screw Steel Cplg	8	12.09	C	0.97	0.05	E	0.40
2278	1/2" 1-Hole Strap	9	5.55	C	0.50	2.29	C	0.21
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	2	82.66	C	1.65	0.18	E	0.36
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
4791	4" Square Flat Blank Cover w/KO	2	41.83	C	0.84	0.07	E	0.14
8068	10x1" TEK Screw	15	6.94	C	1.04	0.01	E	0.15
	--- Entrance Release Total ---				27.75			4.43
--- A-1 Director/Owner Video ---								
1000	1/2" EMT	112	21.66	C	24.26	2.50	C	2.80
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	12	12.09	C	1.45	0.05	E	0.60
2278	1/2" 1-Hole Strap	14	5.55	C	0.78	2.29	C	0.32
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	2	126.49	C	2.53	0.20	E	0.40
2731	4" Square-1G Plaster Ring-5/8"D	2	33.13	C	0.66	0.07	E	0.14
6839	Red Wirenuts	4	109.34	M	0.44	1.75	C	0.07
8068	10x1" TEK Screw	20	6.94	C	1.39	0.01	E	0.20
8261	Grndscr&Bare Pigtail	2	67.78	C	1.36	1.20	C	0.02
	--- A-1 Director/Owner Video Total ---				33.33			4.75
--- Foyer Conduit To Mech Rm ---								
1000	1/2" EMT	100	21.66	C	21.66	2.50	C	2.50
1436	1/2" Set Screw Steel Conn	2	11.49	C	0.23	0.05	E	0.10
1556	1/2" Set Screw Steel Cplg	11	12.09	C	1.33	0.05	E	0.55
2278	1/2" 1-Hole Strap	9	5.55	C	0.50	2.29	C	0.21
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	1	126.49	C	1.26	0.20	E	0.20
2731	4" Square-1G Plaster Ring-5/8"D	1	33.13	C	0.33	0.07	E	0.07
8068	10x1" TEK Screw	12	6.94	C	0.83	0.01	E	0.12
	--- Foyer Conduit To Mech Rm Total ---				26.14			3.75
--- A-20,21 Lighting HR ---								
1000	1/2" EMT	255	21.66	C	55.23	2.50	C	6.38
1436	1/2" Set Screw Steel Conn	28	11.49	C	3.22	0.05	E	1.40
1556	1/2" Set Screw Steel Cplg	26	12.09	C	3.08	0.05	E	1.28
2278	1/2" 1-Hole Strap	32	5.55	C	1.77	2.29	C	0.73
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	8	82.66	C	6.61	0.18	E	1.44
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	6	126.49	C	7.59	0.20	E	1.20
2736	4" Square-2G Plaster Ring-5/8"D	6	51.58	C	3.09	0.07	E	0.42
4790	4" Square Flat Blank Cover	8	25.73	C	2.06	0.07	E	0.56
8261	Grndscr&Bare Pigtail	12	67.78	C	8.13	1.20	C	0.14
	--- A-20,21 Lighting HR Total ---				90.78			13.55
--- A-22,23 Lighting HR ---								
1000	1/2" EMT	236	21.66	C	51.12	2.50	C	5.90
1436	1/2" Set Screw Steel Conn	28	11.49	C	3.22	0.05	E	1.40
1556	1/2" Set Screw Steel Cplg	21	12.09	C	2.48	0.05	E	1.03

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2278	1/2" 1-Hole Strap	29	5.55	C	1.60	2.29	C	0.66
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	8	82.66	C	6.61	0.18	E	1.44
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	6	126.49	C	7.59	0.20	E	1.20
2736	4" Square-2G Plaster Ring-5/8"D	6	51.58	C	3.09	0.07	E	0.42
4790	4" Square Flat Blank Cover	8	25.73	C	2.06	0.07	E	0.56
8261	Grndscr&Bare Pigtail	12	67.78	C	8.13	1.20	C	0.14
--- A-22,23 Lighting HR Total ---					85.90			12.75
--- A-24,25 Lighting HR ---								
1000	1/2" EMT	210	21.66	C	45.49	2.50	C	5.25
1436	1/2" Set Screw Steel Conn	22	11.49	C	2.53	0.05	E	1.10
1556	1/2" Set Screw Steel Cplg	20	12.09	C	2.36	0.05	E	0.98
2278	1/2" 1-Hole Strap	26	5.55	C	1.44	2.29	C	0.59
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	6	82.66	C	4.96	0.18	E	1.08
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	6	126.49	C	7.59	0.20	E	1.20
2731	4" Square-1G Plaster Ring-5/8"D	1	33.13	C	0.33	0.07	E	0.07
2736	4" Square-2G Plaster Ring-5/8"D	5	51.58	C	2.58	0.07	E	0.35
4790	4" Square Flat Blank Cover	6	25.73	C	1.54	0.07	E	0.42
8261	Grndscr&Bare Pigtail	9	67.78	C	6.10	1.20	C	0.11
--- A-24,25 Lighting HR Total ---					74.92			11.15
--- A-26,27 Lighting HR ---								
1000	1/2" EMT	206	21.66	C	44.62	2.50	C	5.15
1436	1/2" Set Screw Steel Conn	22	11.49	C	2.53	0.05	E	1.10
1556	1/2" Set Screw Steel Cplg	18	12.09	C	2.12	0.05	E	0.88
2278	1/2" 1-Hole Strap	23	5.55	C	1.27	2.29	C	0.52
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	7	82.66	C	5.79	0.18	E	1.26
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	8	126.49	C	10.12	0.20	E	1.60
2726	4" Square-3/0 Plaster Ring-5/8"D	3	34.45	C	1.03	0.07	E	0.21
2731	4" Square-1G Plaster Ring-5/8"D	3	33.13	C	0.99	0.07	E	0.21
2736	4" Square-2G Plaster Ring-5/8"D	5	51.58	C	2.58	0.07	E	0.35
4790	4" Square Flat Blank Cover	7	25.73	C	1.80	0.07	E	0.49
8261	Grndscr&Bare Pigtail	11	67.78	C	7.46	1.20	C	0.13
--- A-26,27 Lighting HR Total ---					80.31			11.90
--- A- 28,29 Lighting HR ---								
1000	1/2" EMT	239	21.66	C	51.77	2.50	C	5.98
1436	1/2" Set Screw Steel Conn	36	11.49	C	4.14	0.05	E	1.80
1556	1/2" Set Screw Steel Cplg	25	12.09	C	2.96	0.05	E	1.23
2278	1/2" 1-Hole Strap	29	5.55	C	1.60	2.29	C	0.66
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	9	82.66	C	7.44	0.18	E	1.62
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	7	126.49	C	8.85	0.20	E	1.40
2591	3G Box	1	438.31	C	4.38	0.16	E	0.16
2736	4" Square-2G Plaster Ring-5/8"D	5	51.58	C	2.58	0.07	E	0.35
4790	4" Square Flat Blank Cover	9	25.73	C	2.32	0.07	E	0.63
8261	Grndscr&Bare Pigtail	15	67.78	C	10.17	1.20	C	0.18
--- A- 28,29 Lighting HR Total ---					96.21			14.01
--- A-30 Lighting HR ---								
1000	1/2" EMT	85	21.66	C	18.41	2.50	C	2.13
1436	1/2" Set Screw Steel Conn	4	11.49	C	0.46	0.05	E	0.20
1556	1/2" Set Screw Steel Cplg	10	12.09	C	1.15	0.05	E	0.48
2278	1/2" 1-Hole Strap	11	5.55	C	0.60	2.29	C	0.25

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	1	82.66	C	0.83	0.18	E	0.18
4790	4" Square Flat Blank Cover	1	25.73	C	0.26	0.07	E	0.07
--- A-30 Lighting HR Total ---					21.71			3.31
--- A-40,41 Exterior Lighting ---								
1001	3/4" EMT	400	39.93	C	159.72	2.60	C	10.40
1437	3/4" Set Screw Steel Conn	34	18.68	C	6.35	0.06	E	2.04
1557	3/4" Set Screw Steel Cplg	40	19.21	C	7.68	0.06	E	2.40
2279	3/4" 1-Hole Strap	50	8.42	C	4.21	2.29	C	1.15
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	17	126.49	C	21.50	0.20	E	3.40
2727	4" Square-3/0 Plaster Ring-3/4"D	17	85.95	C	14.61	0.07	E	1.19
--- A-40,41 Exterior Lighting Total ---					214.07			20.58
--- A-42 Exterior Lighting ---								
1000	1/2" EMT	120	21.66	C	25.99	2.50	C	3.00
1436	1/2" Set Screw Steel Conn	2	11.49	C	0.23	0.05	E	0.10
1556	1/2" Set Screw Steel Cplg	12	12.09	C	1.45	0.05	E	0.60
2278	1/2" 1-Hole Strap	15	5.55	C	0.83	2.29	C	0.34
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	1	82.66	C	0.83	0.18	E	0.18
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
4790	4" Square Flat Blank Cover	1	25.73	C	0.26	0.07	E	0.07
--- A-42 Exterior Lighting Total ---					42.01			4.79
--- A-20 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	125	813.41	M	101.68	12.00	M	1.50
6839	Red Wirenuts	63	109.34	M	6.89	1.75	C	1.10
8257	Seismic wire	50	2.00	E	100.00	0.03	E	1.50
1234705	3/8" MC BX Snap Tite Connector Round	32	70.21	C	22.47	0.06	E	1.92
1235000	3/8" T-Bar Wire Conduit Clip	34	23.65	C	8.04	0.01	E	0.34
--- A-20 Lighting Total ---					251.50			6.86
--- A-21 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	145	813.41	M	117.94	12.00	M	1.74
6839	Red Wirenuts	72	109.34	M	7.87	1.75	C	1.26
8257	Seismic wire	58	2.00	E	116.00	0.03	E	1.74
1234705	3/8" MC BX Snap Tite Connector Round	36	70.21	C	25.28	0.06	E	2.16
1235000	3/8" T-Bar Wire Conduit Clip	42	23.65	C	9.93	0.01	E	0.42
--- A-21 Lighting Total ---					289.44			7.82
--- A-22 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	145	813.41	M	117.94	12.00	M	1.74
6839	Red Wirenuts	72	109.34	M	7.87	1.75	C	1.26
8257	Seismic wire	58	2.00	E	116.00	0.03	E	1.74
1234705	3/8" MC BX Snap Tite Connector Round	36	70.21	C	25.28	0.06	E	2.16
1235000	3/8" T-Bar Wire Conduit Clip	42	23.65	C	9.93	0.01	E	0.42
--- A-22 Lighting Total ---					289.44			7.82

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6

Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- A-23 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	145	813.41	M	117.94	12.00	M	1.74
6839	Red Wirenuts	72	109.34	M	7.87	1.75	C	1.26
8257	Seismic wire	58	2.00	E	116.00	0.03	E	1.74
1234705	3/8" MC BX Snap Tite Connector Round	36	70.21	C	25.28	0.06	E	2.16
1235000	3/8" T-Bar Wire Conduit Clip	42	23.65	C	9.93	0.01	E	0.42
--- A-23 Lighting Total ---					289.44			7.82
--- A-24 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	95	813.41	M	77.27	12.00	M	1.14
6839	Red Wirenuts	39	109.34	M	4.26	1.75	C	0.68
8257	Seismic wire	38	2.00	E	76.00	0.03	E	1.14
1234705	3/8" MC BX Snap Tite Connector Round	20	70.21	C	14.04	0.06	E	1.20
1235000	3/8" T-Bar Wire Conduit Clip	24	23.65	C	5.68	0.01	E	0.24
--- A-24 Lighting Total ---					189.67			4.90
--- A-25 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	65	813.41	M	52.87	12.00	M	0.78
6839	Red Wirenuts	30	109.34	M	3.28	1.75	C	0.53
8257	Seismic wire	22	2.00	E	44.00	0.03	E	0.66
1234705	3/8" MC BX Snap Tite Connector Round	14	70.21	C	9.83	0.06	E	0.84
1235000	3/8" T-Bar Wire Conduit Clip	16	23.65	C	3.78	0.01	E	0.16
--- A-25 Lighting Total ---					126.18			3.47
--- A-26 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	95	813.41	M	77.27	12.00	M	1.14
6839	Red Wirenuts	39	109.34	M	4.26	1.75	C	0.68
8257	Seismic wire	38	2.00	E	76.00	0.03	E	1.14
1234705	3/8" MC BX Snap Tite Connector Round	20	70.21	C	14.04	0.06	E	1.20
1235000	3/8" T-Bar Wire Conduit Clip	24	23.65	C	5.68	0.01	E	0.24
--- A-26 Lighting Total ---					189.67			4.90
--- A-27 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	3	534.87	C	16.05	0.18	E	0.54
2727	4" Square-3/0 Plaster Ring-3/4"D	3	85.95	C	2.58	0.07	E	0.21
2927	12/3 Aluminum Clad MC Cable	150	813.41	M	122.01	12.00	M	1.80
6839	Red Wirenuts	54	109.34	M	5.90	1.75	C	0.95
8257	Seismic wire	52	2.00	E	104.00	0.03	E	1.56
8275	3/8" 1-Hole Strap	14	12.70	C	1.78	2.29	C	0.32
1234705	3/8" MC BX Snap Tite Connector Round	34	70.21	C	23.87	0.06	E	2.04
1235000	3/8" T-Bar Wire Conduit Clip	40	23.65	C	9.46	0.01	E	0.40
--- A-27 Lighting Total ---					285.65			7.82
--- A-28 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	4	534.87	C	21.39	0.18	E	0.72

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2727	4" Square-3/0 Plaster Ring-3/4"D	4	85.95	C	3.44	0.07	E	0.28
2927	12/3 Aluminum Clad MC Cable	125	813.41	M	101.68	12.00	M	1.50
6839	Red Wirenuts	54	109.34	M	5.90	1.75	C	0.95
8257	Seismic wire	42	2.00	E	84.00	0.03	E	1.26
1234705	3/8" MC BX Snap Tite Connector Round	30	70.21	C	21.06	0.06	E	1.80
1235000	3/8" T-Bar Wire Conduit Clip	40	23.65	C	9.46	0.01	E	0.40
--- A-28 Lighting Total ---					246.93			6.91
--- A-29 Lighting ---								
2699	Hung Ceiling Box w/24" Bars-Comb KO's	2	534.87	C	10.70	0.18	E	0.36
2727	4" Square-3/0 Plaster Ring-3/4"D	2	85.95	C	1.72	0.07	E	0.14
2927	12/3 Aluminum Clad MC Cable	110	813.41	M	89.48	12.00	M	1.32
6839	Red Wirenuts	45	109.34	M	4.92	1.75	C	0.79
8257	Seismic wire	10	2.00	E	20.00	0.03	E	0.30
1234705	3/8" MC BX Snap Tite Connector Round	26	70.21	C	18.25	0.06	E	1.56
1235000	3/8" T-Bar Wire Conduit Clip	36	23.65	C	8.51	0.01	E	0.36
--- A-29 Lighting Total ---					153.58			4.83
--- A-30 Lighting ---								
2928	12/4 Aluminum Clad MC Cable	100	813.41	M	81.34	15.00	M	1.50
6839	Red Wirenuts	45	109.34	M	4.92	1.75	C	0.79
8257	Seismic wire	28	2.00	E	56.00	0.03	E	0.84
1234705	3/8" MC BX Snap Tite Connector Round	14	70.21	C	9.83	0.06	E	0.84
1235000	3/8" T-Bar Wire Conduit Clip	20	23.65	C	4.73	0.01	E	0.20
--- A-30 Lighting Total ---					156.82			4.17
--- FA ZN-3 Smoke Detectors ---								
1000	1/2" EMT	115	21.66	C	24.91	2.50	C	2.88
1121	1/2" Steel Flex	25	42.25	C	10.56	1.75	C	0.44
1436	1/2" Set Screw Steel Conn	10	11.49	C	1.15	0.05	E	0.50
1556	1/2" Set Screw Steel Cplg	12	12.09	C	1.39	0.05	E	0.58
1878	1/2" Die Cast Screw-In Flex Conn	10	26.32	C	2.63	0.07	E	0.70
2278	1/2" 1-Hole Strap	14	5.55	C	0.80	2.29	C	0.33
2279	3/4" 1-Hole Strap	5	8.42	C	0.42	2.29	C	0.11
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	5	82.66	C	4.13	0.18	E	0.90
2699	Hung Ceiling Box w/24" Bars-Comb KO's	5	534.87	C	26.74	0.18	E	0.90
2727	4" Square-3/0 Plaster Ring-3/4"D	5	85.95	C	4.30	0.07	E	0.35
4790	4" Square Flat Blank Cover	5	25.73	C	1.29	0.07	E	0.35
8257	Seismic wire	5	2.00	E	10.00	0.03	E	0.15
--- FA ZN-3 Smoke Detectors Total ---					88.32			8.19
--- FA ZN-4 Smoke Detectors ---								
1000	1/2" EMT	320	21.66	C	69.31	2.50	C	8.00
1121	1/2" Steel Flex	80	42.25	C	33.80	1.75	C	1.40
1436	1/2" Set Screw Steel Conn	10	11.49	C	1.15	0.05	E	0.50
1556	1/2" Set Screw Steel Cplg	33	12.09	C	3.93	0.05	E	1.63
1878	1/2" Die Cast Screw-In Flex Conn	32	26.32	C	8.42	0.07	E	2.24
2278	1/2" 1-Hole Strap	40	5.55	C	2.22	2.29	C	0.92
2279	3/4" 1-Hole Strap	16	8.42	C	1.35	2.29	C	0.37
2573	4" Square x 2-1/8" Deep Box (1/2 & 3/4 KO's)	16	82.66	C	13.23	0.18	E	2.88
2699	Hung Ceiling Box w/24" Bars-Comb KO's	16	534.87	C	85.58	0.18	E	2.88
2727	4" Square-3/0 Plaster Ring-3/4"D	16	85.95	C	13.75	0.07	E	1.12
4790	4" Square Flat Blank Cover	16	25.73	C	4.12	0.07	E	1.12

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
8257	Seismic wire	16	2.00	E	32.00	0.03	E	0.48
	--- FA ZN-4 Smoke Detectors Total ---				268.86			23.54
	--- FA ZN-5 Pull Stations ---							
1000	1/2" EMT	241	21.66	C	52.20	2.50	C	6.03
1436	1/2" Set Screw Steel Conn	10	11.49	C	1.15	0.05	E	0.50
1556	1/2" Set Screw Steel Cplg	24	12.09	C	2.91	0.05	E	1.21
2278	1/2" 1-Hole Strap	28	5.55	C	1.58	2.29	C	0.65
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	5	126.49	C	6.32	0.20	E	1.00
2731	4" Square-1G Plaster Ring-5/8"D	5	33.13	C	1.66	0.07	E	0.35
	--- FA ZN-5 Pull Stations Total ---				65.82			9.74
	--- FA ZN-6 Pull Stations ---							
1000	1/2" EMT	234	21.66	C	50.68	2.50	C	5.85
1436	1/2" Set Screw Steel Conn	10	11.49	C	1.15	0.05	E	0.50
1556	1/2" Set Screw Steel Cplg	24	12.09	C	2.91	0.05	E	1.21
2278	1/2" 1-Hole Strap	28	5.55	C	1.58	2.29	C	0.65
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	5	126.49	C	6.32	0.20	E	1.00
2731	4" Square-1G Plaster Ring-5/8"D	5	33.13	C	1.66	0.07	E	0.35
	--- FA ZN-6 Pull Stations Total ---				64.30			9.56
	--- FA ZN-7 Horn/Strobe ---							
1000	1/2" EMT	240	21.66	C	51.98	2.50	C	6.00
1436	1/2" Set Screw Steel Conn	28	11.49	C	3.22	0.05	E	1.40
1556	1/2" Set Screw Steel Cplg	24	12.09	C	2.90	0.05	E	1.20
2278	1/2" 1-Hole Strap	30	5.55	C	1.67	2.29	C	0.69
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	14	126.49	C	17.71	0.20	E	2.80
2731	4" Square-1G Plaster Ring-5/8"D	14	33.13	C	4.64	0.07	E	0.98
	--- FA ZN-7 Horn/Strobe Total ---				82.12			13.07
	--- FA ZN-8 Horn/Strobe ---							
1000	1/2" EMT	294	21.66	C	63.68	2.50	C	7.35
1436	1/2" Set Screw Steel Conn	18	11.49	C	2.07	0.05	E	0.90
1556	1/2" Set Screw Steel Cplg	30	12.09	C	3.63	0.05	E	1.50
2278	1/2" 1-Hole Strap	34	5.55	C	1.89	2.29	C	0.78
2574	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	9	126.49	C	11.38	0.20	E	1.80
2731	4" Square-1G Plaster Ring-5/8"D	9	33.13	C	2.98	0.07	E	0.63
	--- FA ZN-8 Horn/Strobe Total ---				85.63			12.96
	--- A-33,39 Parking Lot Lighting ---							
1001	3/4" EMT	10	39.93	C	3.99	2.60	C	0.26
1435	3/4" Set Screw Die Cast Conn	2	31.80	C	0.64	0.06	E	0.12
1596	1" Locknut	1	26.74	C	0.27	0.02	E	0.02
1608	1" Plastic Bushing	1	14.89	C	0.15	0.02	E	0.02
1712	1" Offset Nipple	1	550.13	C	5.50	0.11	E	0.11
5664	30A/4P 120V Mag Ltg Contactor-Nema1 Encl	1	293.95	E	293.95	1.75	E	1.75
5686	SPDT 40A/120V 24 Hr Time Switch w/Res	1	472.24	E	472.24	1.85	E	1.85
5763	12x12x6" Screw Cover Pull Box-Nema 1	1	24.13	E	24.13	1.30	E	1.30
	--- A-33,39 Parking Lot Lighting Total ---				800.87			5.43
	--- FA ZN-1,2 Water Flow/Tamper SW ---							
1001	3/4" EMT	5	39.93	C	2.00	2.60	C	0.13
1144	3/4" Liquidtight (metallic)	12	131.08	C	15.73	2.00	C	0.24

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
1437	3/4" Set Screw Steel Conn	2	18.68	C	0.37	0.06	E	0.12
1931	3/4" Seal-tite Conn (Str)	2	312.24	C	6.24	0.09	E	0.18
1952	3/4" Seal-tite Conn (90 Degree)	2	588.55	C	11.77	0.22	E	0.44
2279	3/4" 1-Hole Strap	4	8.42	C	0.34	2.29	C	0.09
--- FA ZN-1,2 Water Flow/Tamper SW Total ---					36.45			1.20
--- MSB ---								
1189	1" PVC Conduit	30	23.88	C	7.16	1.75	C	0.53
2281	1-1/4" 1-Hole Strap	8	27.12	C	2.17	2.44	C	0.20
--- MSB Total ---					9.33			0.73
--- Telephone/Data Outlet ---								
1001	3/4" EMT	280	39.93	C	111.80	2.60	C	7.28
1445	3/4" Set Screw Steel Conn	56	25.75	C	14.42	0.06	E	3.36
1545	3/4" Set Screw Steel Cplg	1	38.16	C	0.38	0.06	E	0.06
2472	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	28	203.62	C	57.01	0.20	E	5.60
4897	4" Square-1G Plaster Ring-5/8"D	28	55.30	C	15.48	0.07	E	1.96
--- Telephone/Data Outlet Total ---					199.09			18.26
--- 04 Aboveground Branch Conduit Total ---								
					6,853.04			483.89
--- 05 Feeder Wire ---								
--- A-10,12 Future Oven ---								
2792	#8 THHN CU Stranded Wire	94	406.88	M	38.25	6.25	M	0.59
--- A-10,12 Future Oven Total ---					38.25			0.59
--- A-13,15 Dryer ---								
2792	#8 THHN CU Stranded Wire	94	406.88	M	38.25	6.25	M	0.59
--- A-13,15 Dryer Total ---					38.25			0.59
--- Primary Conduit ---								
3109	1/4" Pull Line	63	47.93	M	3.02	6.00	M	0.38
--- Primary Conduit Total ---					3.02			0.38
--- Secondary Conduit ---								
3109	1/4" Pull Line	126	47.93	M	6.04	6.00	M	0.76
--- Secondary Conduit Total ---					6.04			0.76
--- CATV Conduit ---								
3109	1/4" Pull Line	200	47.93	M	9.56	6.00	M	1.20
--- CATV Conduit Total ---					9.56			1.20
--- Telephone Conduit ---								
3109	1/4" Pull Line	200	47.93	M	9.56	6.00	M	1.20
--- Telephone Conduit Total ---					9.56			1.20
--- Panel A ---								
2793	#6 THHN CU Stranded Wire	26	697.27	M	18.13	7.00	M	0.18
2802	#250MCM THHN CU Stranded Wire	104	626.49	C	651.55	22.00	M	2.29
--- Panel A Total ---					669.68			2.47
--- Panel M ---								
2793	#6 THHN CU Stranded Wire	22	697.27	M	15.34	7.00	M	0.15

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2802	#250MCM THHN CU Stranded Wire	88	626.49	C	551.31	22.00	M	1.94
	--- Panel M Total ---				566.65			2.09
	--- Panel B ---							
2792	#8 THHN CU Stranded Wire	30	406.88	M	12.21	6.25	M	0.19
2797	#1 THHN CU Stranded Wire	120	2,180.30	M	261.64	11.00	M	1.32
	--- Panel B Total ---				273.85			1.51
	--- MSB ---							
3096	#2/0 Stranded Bare Copper Wire	40	1,977.70	M	79.11	22.85	M	0.91
	--- MSB Total ---				79.11			0.91
	--- 05 Feeder Wire Total ---				1,693.97			11.70
	--- 06 Branch Wire ---							
	--- A-10,12 Future Oven ---							
2791	#10 THHN CU Stranded Wire	44	250.82	M	11.06	6.00	M	0.26
	--- A-10,12 Future Oven Total ---				11.06			0.26
	--- A-13,15 Dryer ---							
2791	#10 THHN CU Stranded Wire	44	250.82	M	11.06	6.00	M	0.26
	--- A-13,15 Dryer Total ---				11.06			0.26
	--- A-17,19 Receptacle ---							
2787	#12 THHN CU Solid Wire	470	143.46	M	67.48	5.50	M	2.59
	--- A-17,19 Receptacle Total ---				67.48			2.59
	--- A-35,37 Fire Alarm, GWH-1 ---							
2787	#12 THHN CU Solid Wire	544	143.46	M	78.04	5.50	M	2.99
	--- A-35,37 Fire Alarm, GWH-1 Total ---				78.04			2.99
	--- A-36,38 Dishwasher, Microwave ---							
2787	#12 THHN CU Solid Wire	332	143.46	M	47.63	5.50	M	1.83
3106	3Ft. Appliance Pig-tail	1	6.02	E	6.02	0.50	E	0.50
	--- A-36,38 Dishwasher, Microwave Total ---				53.65			2.33
	--- B-1,14,16 Bbd Heat, Receptacle ---							
2787	#12 THHN CU Solid Wire	1,324	143.46	M	189.91	5.50	M	7.28
	--- B-1,14,16 Bbd Heat, Receptacle Total ---				189.91			7.28
	--- B-7,9,11 Receptacle ---							
2787	#12 THHN CU Solid Wire	1,550	143.46	M	222.36	5.50	M	8.53
	--- B-7,9,11 Receptacle Total ---				222.36			8.53
	--- B-10,12,13 Receptacle ---							
2787	#12 THHN CU Solid Wire	1,744	143.46	M	250.19	5.50	M	9.59
	--- B-10,12,13 Receptacle Total ---				250.19			9.59
	--- B-15,17 Receptacle ---							
2787	#12 THHN CU Solid Wire	968	143.46	M	138.87	5.50	M	5.32
	--- B-15,17 Receptacle Total ---				138.87			5.32
	--- B-24,25,27 Microwave, Receptac ---							

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
2787	#12 THHN CU Solid Wire	572	143.46	M	82.06	5.50	M	3.15
	--- B-24,25,27 Microwave, Receptac Total ---				82.06			3.15
	--- B-3,4 Freezer, Refrigerator ---							
2787	#12 THHN CU Solid Wire	188	143.46	M	26.97	5.50	M	1.03
	--- B-3,4 Freezer, Refrigerator Total ---				26.97			1.03
	--- B-19,21,6 Receptacle, Refer ---							
2787	#12 THHN CU Solid Wire	1,200	143.46	M	172.15	5.50	M	6.60
	--- B-19,21,6 Receptacle, Refer Total ---				172.15			6.60
	--- B-8,28,30 Refrigerator, Recept ---							
2787	#12 THHN CU Solid Wire	325	143.46	M	46.62	5.50	M	1.79
	--- B-8,28,30 Refrigerator, Recept Total ---				46.62			1.79
	--- B-29 Exterior Receptacles ---							
2787	#12 THHN CU Solid Wire	1,080	143.46	M	154.94	5.50	M	5.94
	--- B-29 Exterior Receptacles Total ---				154.94			5.94
	--- B-22 EDF-1 ---							
2787	#12 THHN CU Solid Wire	180	143.46	M	25.82	5.50	M	0.99
	--- B-22 EDF-1 Total ---				25.82			0.99
	--- B-18,26 Receptacle, Time Clock ---							
2787	#12 THHN CU Solid Wire	192	143.46	M	27.54	5.50	M	1.06
	--- B-18,26 Receptacle, Time Clock Total ---				27.54			1.06
	--- B-2,20 Receptacles ---							
2787	#12 THHN CU Solid Wire	416	143.46	M	59.68	5.50	M	2.29
	--- B-2,20 Receptacles Total ---				59.68			2.29
	--- M-1,3,5 AC-1 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
	--- M-1,3,5 AC-1 Total ---				89.54			2.14
	--- M-7,9,11 AC-2 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
	--- M-7,9,11 AC-2 Total ---				89.54			2.14
	--- M-13,15,17 AC-3 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
	--- M-13,15,17 AC-3 Total ---				89.54			2.14
	--- M-19,21,23 AC-4 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
	--- M-19,21,23 AC-4 Total ---				89.54			2.14
	--- M-2,4,6 AC-5 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
	--- M-2,4,6 AC-5 Total ---				89.54			2.14
	--- M-8,10,12 AC-6 ---							
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- M-8,10,12 AC-6 Total ---					89.54			2.14
--- M-14,16,18 AC-7 ---								
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
--- M-14,16,18 AC-7 Total ---					89.54			2.14
--- M-20,22,24 AC-8 ---								
2791	#10 THHN CU Stranded Wire	357	250.82	M	89.54	6.00	M	2.14
--- M-20,22,24 AC-8 Total ---					89.54			2.14
--- A-31 Duct Smoke Detectors ---								
2787	#12 THHN CU Solid Wire	558	143.46	M	79.99	5.50	M	3.07
--- A-31 Duct Smoke Detectors Total ---					79.99			3.07
--- Door Bell ---								
2972	3 Cond Thermostat Wire	40	72.76	M	2.91	8.55	M	0.34
--- Door Bell Total ---					2.91			0.34
--- DVR System ---								
2978	TV CABLE (RG-6)	125	247.38	M	30.92	3.50	M	0.44
--- DVR System Total ---					30.92			0.44
--- B-23 Wireless Transmitter ---								
2787	#12 THHN CU Solid Wire	315	143.46	M	45.19	5.50	M	1.73
--- B-23 Wireless Transmitter Total ---					45.19			1.73
--- Handkey Unit ---								
1234687	Non-Plenum Cat 5e 24gauge 4pair	200	98.46	M	19.69	8.05	M	1.61
--- Handkey Unit Total ---					19.69			1.61
--- Entrance Release ---								
1234687	Non-Plenum Cat 5e 24gauge 4pair	110	98.46	M	10.83	8.05	M	0.89
--- Entrance Release Total ---					10.83			0.89
--- A-1 Director/Owner Video ---								
2787	#12 THHN CU Solid Wire	336	143.46	M	48.20	5.50	M	1.85
--- A-1 Director/Owner Video Total ---					48.20			1.85
--- A-20,21 Lighting HR ---								
2787	#12 THHN CU Solid Wire	975	143.46	M	139.87	5.50	M	5.36
--- A-20,21 Lighting HR Total ---					139.87			5.36
--- A-22,23 Lighting HR ---								
2787	#12 THHN CU Solid Wire	864	143.46	M	123.95	5.50	M	4.75
--- A-22,23 Lighting HR Total ---					123.95			4.75
--- A-24,25 Lighting HR ---								
2787	#12 THHN CU Solid Wire	760	143.46	M	109.03	5.50	M	4.18
--- A-24,25 Lighting HR Total ---					109.03			4.18
--- A-26,27 Lighting HR ---								
2787	#12 THHN CU Solid Wire	624	143.46	M	89.52	5.50	M	3.43
--- A-26,27 Lighting HR Total ---					89.52			3.43

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- A- 28,29 Lighting HR ---								
2787	#12 THHN CU Solid Wire	1,035	143.46	M	148.48	5.50	M	5.69
	--- A- 28,29 Lighting HR Total ---				148.48			5.69
--- A-30 Lighting HR ---								
2787	#12 THHN CU Solid Wire	255	143.46	M	36.58	5.50	M	1.40
	--- A-30 Lighting HR Total ---				36.58			1.40
--- A-40,41 Exterior Lighting ---								
2787	#12 THHN CU Solid Wire	2,100	143.46	M	301.27	5.50	M	11.55
	--- A-40,41 Exterior Lighting Total ---				301.27			11.55
--- A-42 Exterior Lighting ---								
2787	#12 THHN CU Solid Wire	378	143.46	M	54.23	5.50	M	2.08
	--- A-42 Exterior Lighting Total ---				54.23			2.08
--- FA ZN-3 Smoke Detectors ---								
2789	#14 THHN CU Stranded Wire	342	119.18	M	40.76	4.50	M	1.54
	--- FA ZN-3 Smoke Detectors Total ---				40.76			1.54
--- FA ZN-4 Smoke Detectors ---								
2789	#14 THHN CU Stranded Wire	740	119.18	M	88.19	4.50	M	3.33
	--- FA ZN-4 Smoke Detectors Total ---				88.19			3.33
--- FA ZN-5 Pull Stations ---								
2789	#14 THHN CU Stranded Wire	502	119.18	M	59.83	4.50	M	2.26
	--- FA ZN-5 Pull Stations Total ---				59.83			2.26
--- FA ZN-6 Pull Stations ---								
2789	#14 THHN CU Stranded Wire	488	119.18	M	58.16	4.50	M	2.20
	--- FA ZN-6 Pull Stations Total ---				58.16			2.20
--- FA ZN-7 Horn/Strobe ---								
2786	#14 THHN CU Solid Wire	504	94.94	M	47.85	4.50	M	2.27
2790	#12 THHN CU Stranded Wire	504	165.61	M	83.47	5.50	M	2.77
	--- FA ZN-7 Horn/Strobe Total ---				131.32			5.04
--- FA ZN-8 Horn/Strobe ---								
2786	#14 THHN CU Solid Wire	588	94.94	M	55.82	4.50	M	2.65
2790	#12 THHN CU Stranded Wire	588	165.61	M	97.38	5.50	M	3.23
	--- FA ZN-8 Horn/Strobe Total ---				153.20			5.88
--- A-33,39 Parking Lot Lighting ---								
2791	#10 THHN CU Stranded Wire	3,360	250.82	M	842.76	6.00	M	20.16
6895	Wire Soap (Quarts)	1	3.77	E	3.77	0.75	E	0.75
	--- A-33,39 Parking Lot Lighting Total ---				846.53			20.91
--- FA ZN-1,2 Water Flow/Tamper SW ---								
2790	#12 THHN CU Stranded Wire	525	165.61	M	86.95	5.50	M	2.89
	--- FA ZN-1,2 Water Flow/Tamper SW Total --				86.95			2.89
--- 06 Branch Wire Total ---								
					5,040.32			171.54

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- 07 Light Fixtures ---								
--- A-40,41 Exterior Lighting ---								
EV-1	Emerg Light w/Batt Pack	12	QUOTE	1	0.00	1.50	E	18.00
WP-1	H.I.D. Wall Pack Fixture	4	QUOTE	1	0.00	0.90	E	3.60
--- A-40,41 Exterior Lighting Total ---					0.00			21.60
--- A-20 Lighting ---								
4991	T-Bar Clip	48	116.89	C	56.11	0.04	E	1.92
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
22995	F28 T5 Cool White 48" Fluor Lamp	30	QUOTE	1	0.00	0.03	E	0.90
A-1	2'x4' Fluor Lay-In	10	QUOTE	1	0.00	0.45	E	4.50
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
--- A-20 Lighting Total ---					56.11			9.29
--- A-21 Lighting ---								
4991	T-Bar Clip	48	116.89	C	56.11	0.04	E	1.92
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
22995	F28 T5 Cool White 48" Fluor Lamp	36	QUOTE	1	0.00	0.03	E	1.08
A-1	2'x4' Fluor Lay-In	12	QUOTE	1	0.00	0.45	E	5.40
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
--- A-21 Lighting Total ---					56.11			10.37
--- A-22 Lighting ---								
4991	T-Bar Clip	56	116.89	C	65.46	0.04	E	2.24
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
22995	F28 T5 Cool White 48" Fluor Lamp	36	QUOTE	1	0.00	0.03	E	1.08
A-1	2'x4' Fluor Lay-In	12	QUOTE	1	0.00	0.45	E	5.40
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
--- A-22 Lighting Total ---					65.46			10.69
--- A-23 Lighting ---								
4991	T-Bar Clip	56	116.89	C	65.46	0.04	E	2.24
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
22995	F28 T5 Cool White 48" Fluor Lamp	36	QUOTE	1	0.00	0.03	E	1.08
A-1	2'x4' Fluor Lay-In	12	QUOTE	1	0.00	0.45	E	5.40
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
--- A-23 Lighting Total ---					65.46			10.69
--- A-24 Lighting ---								
4991	T-Bar Clip	36	116.89	C	42.08	0.04	E	1.44
5100	F32 T8 Cool White 32W 48" Fluor Lamp	6	QUOTE	1	0.00	0.03	E	0.18
22995	F28 T5 Cool White 48" Fluor Lamp	18	QUOTE	1	0.00	0.03	E	0.54
A-1	2'x4' Fluor Lay-In	6	QUOTE	1	0.00	0.45	E	2.70
A-2	2'x4' Fluor Lay-In	3	QUOTE	1	0.00	0.45	E	1.35
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-24 Lighting Total ---				42.08			7.16
	--- A-25 Lighting ---							
4991	T-Bar Clip	20	116.89	C	23.38	0.04	E	0.80
22995	F28 T5 Cool White 48" Fluor Lamp	15	QUOTE	1	0.00	0.03	E	0.45
A-1	2'x4' Fluor Lay-In	5	QUOTE	1	0.00	0.45	E	2.25
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-25 Lighting Total ---				23.38			4.45
	--- A-26 Lighting ---							
4991	T-Bar Clip	36	116.89	C	42.08	0.04	E	1.44
5100	F32 T8 Cool White 32W 48" Fluor Lamp	6	QUOTE	1	0.00	0.03	E	0.18
22995	F28 T5 Cool White 48" Fluor Lamp	18	QUOTE	1	0.00	0.03	E	0.54
A-1	2'x4' Fluor Lay-In	6	QUOTE	1	0.00	0.45	E	2.70
A-2	2'x4' Fluor Lay-In	3	QUOTE	1	0.00	0.45	E	1.35
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-26 Lighting Total ---				42.08			7.16
	--- A-27 Lighting ---							
4991	T-Bar Clip	44	116.89	C	51.43	0.04	E	1.76
5100	F32 T8 Cool White 32W 48" Fluor Lamp	22	QUOTE	1	0.00	0.03	E	0.66
22995	F28 T5 Cool White 48" Fluor Lamp	18	QUOTE	1	0.00	0.03	E	0.54
A-1	2'x4' Fluor Lay-In	6	QUOTE	1	0.00	0.45	E	2.70
A-2	2'x4' Fluor Lay-In	5	QUOTE	1	0.00	0.45	E	2.25
A-3	2'x4' Recessed Fluor	2	QUOTE	1	0.00	0.55	E	1.10
B-1	4' Fluor Strip	3	QUOTE	1	0.00	0.40	E	1.20
P-1	Compact Fluor Surace/Ceiling Mtd	2	QUOTE	1	0.00	0.45	E	0.90
P-2	Compact Fluor Surace/Ceiling Mtd	2	QUOTE	1	0.00	0.45	E	0.90
W-1	Compact Fluor Recessed Downlight	3	QUOTE	1	0.00	0.45	E	1.35
X	Exit Fixture	2	QUOTE	1	0.00	0.40	E	0.80
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-27 Lighting Total ---				51.43			14.71
	--- A-28 Lighting ---							
4991	T-Bar Clip	40	116.89	C	46.76	0.04	E	1.60
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
22995	F28 T5 Cool White 48" Fluor Lamp	24	QUOTE	1	0.00	0.03	E	0.72
A-1	2'x4' Fluor Lay-In	8	QUOTE	1	0.00	0.45	E	3.60
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-28 Lighting Total ---				46.76			7.89
	--- A-29 Lighting ---							
4991	T-Bar Clip	8	116.89	C	9.35	0.04	E	0.32
5100	F32 T8 Cool White 32W 48" Fluor Lamp	4	QUOTE	1	0.00	0.03	E	0.12
A-2	2'x4' Fluor Lay-In	2	QUOTE	1	0.00	0.45	E	0.90
X	Exit Fixture	1	QUOTE	1	0.00	0.40	E	0.40
X-1	Exit/Dual Head Emerg Fixt w/Batt Pack	1	QUOTE	1	0.00	0.55	E	0.55
	--- A-29 Lighting Total ---				9.35			2.29

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- A-30 Lighting ---								
4991	T-Bar Clip	28	116.89	C	32.73	0.04	E	1.12
5100	F32 T8 Cool White 32W 48" Fluor Lamp	14	QUOTE	1	0.00	0.03	E	0.42
A-2	2'x4' Fluor Lay-In	7	QUOTE	1	0.00	0.45	E	3.15
--- A-30 Lighting Total ---					32.73			4.69
--- A-33,39 Parking Lot Lighting ---								
5273	20' Steel Pole	8	QUOTE	1	0.00	4.25	E	34.00
P1	H.I.D. Single Head Pole Top Fixture	6	QUOTE	1	0.00	1.50	E	9.00
P2	H.I.D. Single Head Pole Top Fixture	2	QUOTE	1	0.00	1.50	E	3.00
--- A-33,39 Parking Lot Lighting Total ---					0.00			46.00
--- 07 Light Fixtures Total ---					490.95			156.99
--- 08 Devices and Trim ---								
--- A-10,12 Future Oven ---								
4610	50A/250V 2P3W Sgl Rcpt (6-50R)	1	18.57	E	18.57	0.23	E	0.23
4799	Dryer/Range Flush Cover	1	119.16	C	1.19	0.05	E	0.05
--- A-10,12 Future Oven Total ---					19.76			0.28
--- A-13,15 Dryer ---								
4610	50A/250V 2P3W Sgl Rcpt (6-50R)	1	18.57	E	18.57	0.23	E	0.23
4799	Dryer/Range Flush Cover	1	119.16	C	1.19	0.05	E	0.05
--- A-13,15 Dryer Total ---					19.76			0.28
--- A-17,19 Receptacle ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
--- A-17,19 Receptacle Total ---					4.11			0.42
--- A-35,37 Fire Alarm, GWH-1 ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
--- A-35,37 Fire Alarm, GWH-1 Total ---					4.11			0.42
--- A-36,38 Dishwasher, Microwave ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
--- A-36,38 Dishwasher, Microwave Total ---					4.11			0.42
--- B-1,14,16 Bbd Heat, Receptacle ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	12	113.69	C	13.64	0.15	E	1.80
4697	1G SS Dup Rcpt Plate	12	91.80	C	11.02	0.06	E	0.72
--- B-1,14,16 Bbd Heat, Receptacle Total ---					24.66			2.52
--- B-7,9,11 Receptacle ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	12	113.69	C	13.64	0.15	E	1.80
4697	1G SS Dup Rcpt Plate	12	91.80	C	11.02	0.06	E	0.72
--- B-7,9,11 Receptacle Total ---					24.66			2.52
--- B-10,12,13 Receptacle ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	15	113.69	C	17.05	0.15	E	2.25
4697	1G SS Dup Rcpt Plate	15	91.80	C	13.77	0.06	E	0.90

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- B-10,12,13 Receptacle Total ---					30.82			3.15
--- B-15,17 Receptacle ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	8	113.69	C	9.10	0.15	E	1.20
4697	1G SS Dup Rcpt Plate	8	91.80	C	7.34	0.06	E	0.48
--- B-15,17 Receptacle Total ---					16.44			1.68
--- B-24,25,27 Microwave, Receptac ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	8	113.69	C	9.10	0.15	E	1.20
4697	1G SS Dup Rcpt Plate	8	91.80	C	7.34	0.06	E	0.48
--- B-24,25,27 Microwave, Receptac Total ---					16.44			1.68
--- B-3,4 Freezer, Refrigerator ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
--- B-3,4 Freezer, Refrigerator Total ---					4.11			0.42
--- B-19,21,6 Receptacle, Refer ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	10	113.69	C	11.37	0.15	E	1.50
4697	1G SS Dup Rcpt Plate	10	91.80	C	9.18	0.06	E	0.60
--- B-19,21,6 Receptacle, Refer Total ---					20.55			2.10
--- B-8,28,30 Refrigerator, Recept ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	3	113.69	C	3.41	0.15	E	0.45
4697	1G SS Dup Rcpt Plate	3	91.80	C	2.75	0.06	E	0.18
--- B-8,28,30 Refrigerator, Recept Total ---					6.16			0.63
--- B-29 Exterior Receptacles ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	5	113.69	C	5.68	0.15	E	0.75
4518	20A/125V Spec Grade GFI Dup Rcpt (5-20R)	1	9.77	E	9.77	0.19	E	0.19
4769	1G WP In Use GFI Cover (Vertical)	1	7.35	E	7.35	0.12	E	0.12
4770	1G WP In Use Cover Horizontal	5	7.87	E	39.35	0.12	E	0.60
--- B-29 Exterior Receptacles Total ---					62.15			1.66
--- B-22 EDF-1 ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	1	113.69	C	1.14	0.15	E	0.15
4697	1G SS Dup Rcpt Plate	1	91.80	C	0.92	0.06	E	0.06
--- B-22 EDF-1 Total ---					2.06			0.21
--- B-18,26 Receptacle, Time Clock ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	5	113.69	C	5.68	0.15	E	0.75
4717	4" Square 1G Ind Dup Rcpt Cover	1	67.68	C	0.68	0.07	E	0.07
4721	4" Square-2G Ind Dup Rcpt Cover	2	67.68	C	1.35	0.10	E	0.20
--- B-18,26 Receptacle, Time Clock Total ---					7.71			1.02
--- B-2,20 Receptacles ---								
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	4	113.69	C	4.55	0.15	E	0.60
4697	1G SS Dup Rcpt Plate	1	91.80	C	0.92	0.06	E	0.06
4700	1G SS Decora/GFI Plate	3	104.69	C	3.14	0.05	E	0.15
--- B-2,20 Receptacles Total ---					8.61			0.81
--- M-13,15,17 AC-3 ---								
4518	20A/125V Spec Grade GFI Dup Rcpt (5-20R)	1	9.77	E	9.77	0.19	E	0.19

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
4769	1G WP In Use GFI Cover (Vertical)	1	7.35	E	7.35	0.12	E	0.12
	--- M-13,15,17 AC-3 Total ---				17.12			0.31
	--- M-8,10,12 AC-6 ---							
4518	20A/125V Spec Grade GFI Dup Rcpt (5-20R)	1	9.77	E	9.77	0.19	E	0.19
4769	1G WP In Use GFI Cover (Vertical)	1	7.35	E	7.35	0.12	E	0.12
	--- M-8,10,12 AC-6 Total ---				17.12			0.31
	--- Door Bell ---							
6909	Door Bell Transformer	12	7.13	E	85.56	0.30	E	3.60
	--- Door Bell Total ---				85.56			3.60
	--- B-23 Wireless Transmitter ---							
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
	--- B-23 Wireless Transmitter Total ---				4.11			0.42
	--- A-1 Director/Owner Video ---							
4511	20A/125V Spec Grade Dup Rcpt (5-20R)	2	113.69	C	2.27	0.15	E	0.30
4697	1G SS Dup Rcpt Plate	2	91.80	C	1.84	0.06	E	0.12
	--- A-1 Director/Owner Video Total ---				4.11			0.42
	--- A-20,21 Lighting HR ---							
4459	20A Spec Grade SP Switch	12	161.74	C	19.41	0.15	E	1.80
4703	2G SS Toggle Sw Plate	6	160.63	C	9.64	0.10	E	0.60
	--- A-20,21 Lighting HR Total ---				29.05			2.40
	--- A-22,23 Lighting HR ---							
4459	20A Spec Grade SP Switch	12	161.74	C	19.41	0.15	E	1.80
4703	2G SS Toggle Sw Plate	6	160.63	C	9.64	0.10	E	0.60
	--- A-22,23 Lighting HR Total ---				29.05			2.40
	--- A-24,25 Lighting HR ---							
4459	20A Spec Grade SP Switch	11	161.74	C	17.79	0.15	E	1.65
4703	2G SS Toggle Sw Plate	5	160.63	C	8.03	0.10	E	0.50
	--- A-24,25 Lighting HR Total ---				25.82			2.15
	--- A-26,27 Lighting HR ---							
4459	20A Spec Grade SP Switch	12	161.74	C	19.41	0.15	E	1.80
4696	1G SS Toggle Sw Plate	3	86.06	C	2.58	0.08	E	0.24
4703	2G SS Toggle Sw Plate	5	160.63	C	8.03	0.10	E	0.50
	--- A-26,27 Lighting HR Total ---				30.02			2.54
	--- A- 28,29 Lighting HR ---							
4459	20A Spec Grade SP Switch	13	161.74	C	21.03	0.15	E	1.95
4483	20A Spec Grade 3-Way Switch	2	238.77	C	4.78	0.25	E	0.50
4696	1G SS Toggle Sw Plate	2	86.06	C	1.72	0.08	E	0.16
4703	2G SS Toggle Sw Plate	5	160.63	C	8.03	0.10	E	0.50
	--- A- 28,29 Lighting HR Total ---				35.56			3.11
	--- 08 Devices and Trim Total ---				553.74			37.88
	--- 09 Switchgear ---							

* Target, Labor column 2

Estimateguard Sample Project
Job Number: 6
Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price	U	Ext Price	Labor Hr	U	Ext Lab Hr
--- M-1,3,5 AC-1 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-1,3,5 AC-1 Total ---				87.61			1.35
--- M-7,9,11 AC-2 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-7,9,11 AC-2 Total ---				87.61			1.35
--- M-13,15,17 AC-3 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-13,15,17 AC-3 Total ---				87.61			1.35
--- M-19,21,23 AC-4 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-19,21,23 AC-4 Total ---				87.61			1.35
--- M-2,4,6 AC-5 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-2,4,6 AC-5 Total ---				87.61			1.35
--- M-8,10,12 AC-6 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-8,10,12 AC-6 Total ---				87.61			1.35
--- M-14,16,18 AC-7 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-14,16,18 AC-7 Total ---				87.61			1.35
--- M-20,22,24 AC-8 ---								
3209	60A/3P 240V GD NF Safety Sw-Nema 3R	1	87.61	E	87.61	1.35	E	1.35
	--- M-20,22,24 AC-8 Total ---				87.61			1.35
--- Panel A ---								
		3	0.00	E	0.00	0.00	E	0.00
PNL A	225 Amp Surf Panel-Nema 1	1	QUOTE	2	0.00	14.92	E	14.92
	--- Panel A Total ---				0.00			14.92
--- Panel M ---								
		3	0.00	E	0.00	0.00	E	0.00
3982	25A 3P 120/240V Bolt-On Circuit Breaker	5	53.04	E	265.20	0.40	E	2.00
3985	40A 3P 120/240V Bolt-On Circuit Breaker	3	87.27	E	261.81	0.50	E	1.50
PNL A	225 Amp Surf Panel-Nema 1	1	QUOTE	2	0.00	14.92	E	14.92
	--- Panel M Total ---				527.01			18.42
--- Panel B ---								
		3	0.00	E	0.00	0.00	E	0.00
PNL B	100 Amp Surf Panel-Nema 1	1	QUOTE	2	0.00	12.39	E	12.39
	--- Panel B Total ---				0.00			12.39
--- MSB ---								
3308	600A 250V RK5 Time Delay Fuse	3	74.05	E	222.15	0.10	E	0.30
6671	5/8"x10' Copper Ground Rod	1	16.20	E	16.20	0.33	E	0.33
6675	5/8" Ground Rod Clamp	1	277.24	C	2.77	0.15	E	0.15

* Target, Labor column 2

Estimateguard Sample Project

Job Number: 6

Extension By Phase, And Subtotals By Section

Item #	Description	Quantity	Price U	Ext Price	Labor Hr U	Ext Lab Hr
MSB	600A Main Switchboard/Free Standing-N1	1	QUOTE 2	0.00	53.94 E	53.94
	--- MSB Total ---			241.12		54.72

	--- 09 Switchgear Total ---			1,469.01		111.25

	Job Total			21,148.82		1,424.30